



NOTE:
REPLACEMENT FOR 21 CONIFERS REMOVED AT THE TENNIS COURTS, TO BE A PURCHASED CREDIT AND ARE NOT INCLUDED IN THE PLANTING SCHEDULE.

Overall Planting Schedule				
Quantity	Type Mark	Common Name	Botanical Name	Installed Size
Tree - Ornamental				
17	AGA	Autumn Brilliance Serviceberry	Amelanchier x grandiflora 'Autumn Brilliance'	2 1/2" B&B - Multistem
Tree - Deciduous				
17	BNS	River Birch	Betula nigra	2 1/2" B&B Single Stem
18	COC	Hackberry	Celtis occidentalis	2 1/2" B&B
7	GTD	Street Keeper Honeylocust	Gleditsia triacanthos var. inermis 'Draves'	2 1/2" B&B
18	GTS	Skyline Honeylocust	Gleditsia triacanthos var. inermis 'Skyline'	2 1/2" B&B
4	QBI	Swamp White Oak	Quercus bicolor	2 1/2" B&B
12	QMA	Bur Oak	Quercus macrocarpa	2 1/2" B&B
14	RMP	Red Maple	Acer rubrum	2" cal.
9	UAP	Princeton Elm	Ulmus americana 'Princeton'	2 1/2" B&B
9	UMO	Accolade Elm	Ulmus 'Morton'	2 1/2" B&B
Tree - Coniferous				
10	PAR	Fat Albert Blue Spruce	Picea pungens 'Fat Albert'	8' H. (4" cal.)
4	PGW	White Spruce	Picea glauca	2 1/2" B&B
19	POB	Brun's Serbian Spruce	Picea omorika 'Brun's'	8' H. (4" cal.)
Shrub - Deciduous				
190	CAM	Baton Rouge Dogwood	Cornus alba 'Minbat'	#5 CONT
88	PAT	Russian Sage	Perovskia atriplicifolia	#5 CONT
63	RAG	Gro-low Fragrant Sumac	Rhus aromatica 'Gro-Low'	#5 CONT
Perennial				
6	AMS	Achillea millefolium 'Sunny Seduction'	Sunny Seduction Yarrow	#2 CONT
219	AXM	Achillea x 'Moonshine'	Moonshine Yarrow	#2 CONT
133	CAK	Karl Foerster Feather Reed Grass	Calamagrostis acutiflora 'Karl Foerster'	#2 CONT
137	DPU	Purple Prairie Clover	Dalea purpurea	#2 CONT
46	EYU	Rattlesnake Master	Eryngium yuccifolium	#2 CONT
65	NXF	Walker's Low Catmint	Nepeta x faassenii 'Walker's Low'	#2 CONT
179	SHE	Prairie Dropseed	Sporobolus heterolepis	#2 CONT
177	SNC	Caradonna Meadow Sage	Salvia nemorosa 'Caradonna'	#2 CONT
48	SSM	Blue Heaven Little Bluestem	Schizachyrium scoparium 'MinnblueA'	#2 CONT

Planting Notes

- PLANT SCHEDULE TAKES PRECEDENCE OVER PLAN IF DISCREPANCIES IN QUANTITIES EXIST. SPECIFICATIONS AND DETAILS TAKE PRECEDENCE OVER NOTES.
- CONTRACTOR SHALL REVIEW THE SITE FOR DEFICIENCIES IN THE PLANT MATERIAL SELECTIONS AND OTHER SITE CONDITIONS WHICH MIGHT NEGATIVELY AFFECT PLANT ESTABLISHMENT, SURVIVAL OR WARRANTY. UNSUITABLE PLANT MATERIAL SELECTIONS OR SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING OF WORK.
- NO PLANT MATERIAL SUBSTITUTIONS WILL BE ACCEPTED UNLESS APPROVAL IS REQUESTED OF THE LANDSCAPE ARCHITECT BY THE LANDSCAPE CONTRACTOR PRIOR TO THE SUBMISSION OF BID AND/OR QUOTATION.
- CONTRACTOR RESPONSIBLE FOR LAYOUT AND STAKING OF PLANT MATERIAL. MATERIAL SHALL BE LOCATED AND STAKED AS SHOWN ON PLANS. ALL STAKING AND BASE GRADING TO BE VERIFIED AND APPROVED BY THE LANDSCAPE ARCHITECT IN FIELD PRIOR TO ANY FINAL SURFACE MATERIAL INSTALLATIONS.
- ADJUSTMENTS IN LOCATION OF PROPOSED PLANT MATERIALS MAY BE NEEDED IN FIELD. LANDSCAPE ARCHITECT MUST BE NOTIFIED PRIOR TO ADJUSTMENT OF PLANTS.
- NO PLANTS WILL BE INSTALLED UNTIL FINAL GRADING AND CONSTRUCTION HAVE BEEN COMPLETED IN THE IMMEDIATE AREA. PLANT MATERIALS TO BE INSTALLED PER PLANTING DETAILS.
- CONTRACTOR SHALL COORDINATE THE PHASES OF CONSTRUCTION AND PLANTING INSTALLATION WITH OTHER CONTRACTORS WORKING ON SITE.
- KEEP FINAL ELEVATIONS OF SOIL AND MULCH FROM BLOCKING INTENDED STORM WATER FLOW. SEE CIVIL AND/OR LANDSCAPE DRAWINGS FOR GRADING PLAN.
- SALVAGE TOPSOIL FOR REUSE FROM THE EARTHWORK AREAS AS APPROPRIATE AND/OR AS DIRECTED BY LANDSCAPE ARCHITECT AND STOCKPILE IN LOCATION APPROVED BY OWNER. PROJECT MANAGER TO REVIEW, DIRECT AND APPROVE ALL REQUIRED SOIL CORRECTIONS PRIOR TO BASE MATERIAL PLACEMENT.
- CONTRACTOR SHALL ENSURE THAT SOIL CONDITIONS AND COMPACTION ARE ADEQUATE TO ALLOW FOR PROPER DRAINAGE OF THE PROJECT SITE. UNSUITABLE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING OF WORK. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE PROPER SURFACE AND SUBSURFACE DRAINAGE IN ALL AREAS.
- UNDERGROUND UTILITIES SHALL BE INSTALLED SO THAT TRENCHES DO NOT CUT THROUGH ROOT SYSTEMS OF ANY EXISTING TREES TO REMAIN.
- EDGE AREAS WHERE TURF/SOD MEET PLANTING BEDS AS SHOWN IN PLANS AND AS DESCRIBED IN THE SPECIFICATIONS.
- SOD AREAS DISTURBED DUE TO GRADING SHALL BE REPLACED, UNLESS NOTED OTHERWISE.
- WHERE SOD ADJUTS PAVED SURFACES, FINISHED GRADE OF SOD/SEED SHALL BE HELD 1" BELOW SURFACE ELEVATION OF TRAIL, SLAB, CURB, ETC.
- SOD SHALL BE LAID PARALLEL TO THE CONTOURS AND SHALL HAVE STAGGERED JOINTS ON SLOPES STEEPER THAN 3:1 OR IN DRAINAGE SWALES. SOD SHALL BE STAKED SECURELY.
- CONTRACTOR IS RESPONSIBLE FOR ONGOING MAINTENANCE SUCH AS WATERING AND WEEDING OF NEWLY INSTALLED MATERIALS, AND REPLACEMENTS FOR ENTIRE WARRANTY PERIOD. SEE SPECIFICATIONS. ACTS OF VANDALISM OR DAMAGE WHICH MAY OCCUR PRIOR TO OWNER ACCEPTANCE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Landscape Architect under the laws of the state of Minnesota.

Signed:

Revisions		
No.	Date	Description
1	12/05/22	CUP Submittal

Project Information

Phase:	CUP	Date:	12/05/2022
Project No.:	22-0211	PIC/AIC:	PL

St. Louis Park HS Additions / Renovations

Sheet Title

OVERALL PLANTING PLAN

Sheet Number: L3.00 Current Revision: 1

L3.00 1